

# SPVPP 3.6 kw BOS KIT



# SPVPP 3.6 kw BOS KIT WITH SR.NO.



## SPVPP 3.6kw BOS Items

S.No	POWER PLANT ITEMS	CATEGORY	UOM	3.6 KW 1 SET QTY
1	GI Pipe 25MM X 10FT [148 X 3.048 ]	GI	Nos	1
2	AC Cable 10Sqmm [ RED & BLACK ]	Cable	Mtr	0
3	AC Cable 16Sqmm [ RED & BLACK ]	Cable	Mtr	80
4	AC Cable 25Sqmm [ RED & BLACK ]	Cable	Mtr	0
5	DC Cable 4Sqmm [ RED & BLACK ]	Cable	Mtr	40
6	PVC PIPE 1"	Pvc	Nos	15
7	PVC L Bend 1"	Pvc	Nos	15
8	PVC Elbow 1"	Pvc	Nos	15
9	PVC T 1"	Pvc	Nos	5
10	Flexible Pipe 1"	Electrical	Mtr	1
11	MC4 Connector M/F	Electrical	Set	6
12	Cable Tie 3.6MM X 300MM	Electrical	Pkt	1
13	Kaju Clip 1"	Electrical	Pkt	1
14	PVC Insulation Tape Black	Electrical	Nos	4
15	PVC Insulation Tape Red	Electrical	Nos	4
16	Lugs Pin 10sqmm	Electrical	Nos	0
17	Lugs Ring 10sqmm	Electrical	Nos	0
18	Lugs Pin 16sqmm	Electrical	Nos	30
19	Lugs Ring 16sqmm	Electrical	Nos	36
20	Lugs Pin 25sqmm	Electrical	Nos	0
21	Lugs Ring 25sqmm	Electrical	Nos	0
22	Lugs Pin 4sqmm	Electrical	Nos	10
23	Earthing Rod 1MTR	Earthing	Nos	3
24	Earthing Chamber FRAME 12" X 12"	Earthing	Nos	3
25	Earthing Chemical 5kg	Earthing	Bag	3
26	Earthing Aluminium Strip 25MM X 3MM	Earthing	Kg	7
27	Earthing 5 SPIKE & BASE 25MM	Earthing	Nos	1
28	Nails - 3"	Steel	kg	2
29	Pin fasteners 10mm x 100mm	Steel	Nos	40
30	Rubber Mat - 3mm	Rubber	KG	0.5
31	Inverter stool 1.6" X 2.4" X 0.6"	Wood	Nos	1
32	Inverter stool 1.6" X 2.6" X 0.6"	Wood	Nos	0
33	Inverter stool 2' X 3' X 0.6"	Wood	Nos	0
34	Battery Stand 1.6" X 4' X 0.6"	Battery	Nos	2
35	Battery Stand 3' X 4.6" X 0.6"	Battery	Nos	0