

# SPVPP 6 kw BOS KIT



# SPVPP 6 kw BOS KIT WITH SR.NO.



## SPVPP 6kw BOS Items

S .No	POWER PLANT ITEMS	CATEGORY	UOM	6 KW 1 SET QTY
1	GI Pipe <b>25MM X 10FT [148 X 3.048 ]</b>	GI	Nos	1
2	AC Cable <b>10Sqmm [ RED &amp; BLACK ]</b>	Cable	Mtr	0
3	AC Cable <b>16Sqmm [ RED &amp; BLACK ]</b>	Cable	Mtr	0
4	AC Cable <b>25Sqmm [ RED &amp; BLACK ]</b>	Cable	Mtr	100
5	DC Cable <b>4Sqmm [ RED &amp; BLACK ]</b>	Cable	Mtr	60
6	PVC PIPE <b>1"</b>	Pvc	Nos	15
7	PVC L Bend <b>1"</b>	Pvc	Nos	15
8	PVC Elbow <b>1"</b>	Pvc	Nos	15
9	PVC T <b>1"</b>	Pvc	Nos	5
10	Flexible Pipe <b>1"</b>	Electrical	Mtr	1
11	MC4 Connector <b>M/F</b>	Electrical	Set	8
12	Cable Tie <b>3.6MM X 300MM</b>	Electrical	Pkt	1
13	Kaju Clip <b>1"</b>	Electrical	Pkt	1
14	PVC Insulation Tape <b>Black</b>	Electrical	Nos	4
15	PVC Insulation Tape <b>Red</b>	Electrical	Nos	4
16	Lugs Pin <b>10sqmm</b>	Electrical	Nos	0
17	Lugs Ring <b>10sqmm</b>	Electrical	Nos	0
18	Lugs Pin <b>16sqmm</b>	Electrical	Nos	0
19	Lugs Ring <b>16sqmm</b>	Electrical	Nos	0
20	Lugs Pin <b>25sqmm</b>	Electrical	Nos	30
21	Lugs Ring <b>25sqmm</b>	Electrical	Nos	36
22	Lugs Pin <b>4sqmm</b>	Electrical	Nos	20
23	Earthing Rod <b>1MTR</b>	Earthing	Nos	3
24	Earthing Chamber FRAME <b>12" X 12"</b>	Earthing	Nos	3
25	Earthing Chemical <b>5kg</b>	Earthing	Bag	3
26	Earthing Aluminium Strip <b>25MM X 3MM</b>	Earthing	Kg	7
27	Earthing 5 SPIKE & BASE <b>25MM</b>	Earthing	Nos	1
28	Nails - <b>3"</b>	Steel	kg	2
29	Pin fasteners <b>10mm x 100mm</b>	Steel	Nos	48
30	Rubber Mat - <b>3mm</b>	Rubber	KG	1
31	Inverter stool <b>1.6" X 2.4" X 0.6"</b>	Wood	Nos	0
32	Inverter stool <b>1.6" X 2.6" X 0.6"</b>	Wood	Nos	1
33	Inverter stool <b>2' X 3' X 0.6"</b>	Wood	Nos	0
34	Battery Stand <b>1.6" X 4' X 0.6"</b>	Battery	Nos	6
35	Battery Stand <b>3' X 4.6" X 0.6"</b>	Battery	Nos	0