

# SPVPP 7.2 kw BOS KIT



# SPVPP 7.2 kw BOS KIT WITH SR.NO.



## SPVPP 7.2kw BOS Items

S.No	POWER PLANT ITEMS	CATEGORY	UOM	7.2 KW	1 SET QTY
1	GI Pipe 25MM X 10FT [148 X 3.048 ]	GI	Nos		1
2	AC Cable 10Sqmm [ RED & BLACK ]	Cable	Mtr		0
3	AC Cable 16Sqmm [ RED & BLACK ]	Cable	Mtr		0
4	AC Cable 25Sqmm [ RED & BLACK ]	Cable	Mtr		100
5	DC Cable 4Sqmm [ RED & BLACK ]	Cable	Mtr		80
6	PVC PIPE 1"	Pvc	Nos		15
7	PVC L Bend 1"	Pvc	Nos		15
8	PVC Elbow 1"	Pvc	Nos		15
9	PVC T 1"	Pvc	Nos		5
10	Flexible Pipe 1"	Electrical	Mtr		1
11	MC4 Connector M/F	Electrical	Set		8
12	Cable Tie 3.6MM X 300MM	Electrical	Pkt		1
13	Kaju Clip 1"	Electrical	Pkt		1
14	PVC Insulation Tape Black	Electrical	Nos		5
15	PVC Insulation Tape Red	Electrical	Nos		5
16	Lugs Pin 10sqmm	Electrical	Nos		0
17	Lugs Ring 10sqmm	Electrical	Nos		0
18	Lugs Pin 16sqmm	Electrical	Nos		0
19	Lugs Ring 16sqmm	Electrical	Nos		0
20	Lugs Pin 25sqmm	Electrical	Nos		30
21	Lugs Ring 25sqmm	Electrical	Nos		36
22	Lugs Pin 4sqmm	Electrical	Nos		20
23	Earthing Rod 1MTR	Earthing	Nos		3
24	Earthing Chamber FRAME 12" X 12"	Earthing	Nos		3
25	Earthing Chemical 5kg	Earthing	Bag		3
26	Earthing Aluminium Strip 25MM X 3MM	Earthing	Kg		7
27	Earthing 5 SPIKE & BASE 25MM	Earthing	Nos		1
28	Nails - 3"	Steel	kg		2
29	Pin fasteners 10mm x 100mm	Steel	Nos		96
30	Rubber Mat - 3mm	Rubber	KG		1.5
31	Inverter stool 1.6" X 2.4" X 0.6"	Wood	Nos		0
32	Inverter stool 1.6" X 2.6" X 0.6"	Wood	Nos		1
33	Inverter stool 2' X 3' X 0.6"	Wood	Nos		0
34	Battery Stand 1.6" X 4' X 0.6"	Battery	Nos		6
35	Battery Stand 3' X 4.6" X 0.6"	Battery	Nos		0